BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:-Improvements to Roads and Drains in Ward No 7 Byatarayanapura

No	Description of work	Unit	Mesurement No.	L	B	D	Estimation Cost.Rs 20000000.00 Qty	Rate	Amount
1	18.27 KSRRB M200-15.2. Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cementconcrete, wood work, steel work, including T&P and scaffolding wherevernecessary, sorting the dismantled material, disposal of unserviceablematerial and stacking the serviceable material with all liftsas per specifications. iii)Dismantling Stone Masonry. B. Rubble Stone masonry in cement mortar.No. KBS Pg No 140 ,Item No 18.27.								
	SSM Culvert								
	Yogesh Nagar								
	12th Cross Road	Cum	2	5.00	0.45	0.60	2.70		
	Basic rate	351.00							
	Area weightage 6%	21.06							
	5Km lead & Lift= 57+(2*1.28*5)	69.80							
	Sub Total	**441.86**							
	Total						**2.70**	**441.86**	**1193.02**
2	KSRRB M200-12.2. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M-20. MORTH Specification No. 202. Page No. 139, Item No.18.18 and Pg No.136, Item No.17.4,17.1 (5km lead = 57+2*1.28X5)								
	Culvert Deck Slab								
	Yogesh Nagar								
	12th Cross Road	Cum	1	5	1.5	0.2	1.5		
	Basic rate	557.00							
	Area weightage 6%	33.42							
	5Km lead & Lift= 57+(2*1.28*5)	69.80							
	Sub Total	**660.22**							
	Total						**1.50**	**660.22**	**990.33**
3	KSRRB 300-1. **Earthwork excavation by manual means for roads,** drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1) 5km lead= 57+2.0x1.28x5 =69.80								
	New Drain								
	Nagarajappa Layout								
	1st Cross Road	Cum	2	49	1.05	1.05	108.05		
	2nd Cross Road	Cum	2	65	1.05	1.05	143.33		
	Vayunandhana Layout								
	1st Cross Road	Cum	1	89	1.05	1.05	98.12		
	3rd Cross Road	Cum	1	92	1.05	1.05	101.43		
	Yogesh Nagar								
	11th Cross Road	Cum	2	34	1.05	1.05	74.97		
	9th Cross Road	Cum	2	21	1.2	1.05	52.92		
	7th Cross Road	Cum	2	21	1.2	1.05	52.92		
	10th Cross Road	Cum	2	35	1.2	1.05	88.20		
	12th Cross Road	Cum	2	32	1.2	1.05	80.64		
	Netaji Nagar								
	1st Main Road 4th Cross	Cum	2	59	1.2	1.05	148.68		
	Cross Road	Cum	2	53.5	1.2	1.05	134.82		
	New Culvert								

Scanned by TapScanner

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK : Improvements to Roads and Drains in Ward No 7 Dyatarayanapura

Estimation Cost Rs 26000000.00

Description of work	Unit	No.	L	B	D	Qty	Rate	Amount
KSRRB M200-12.2. Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherevernecessary, stacking the dismantled material, disposal of unserviceablematerial and stacking the serviceable material with all liftsas per specifications. iii)Dismantling Stone Masonry. B. Rubble Stone masonry in cement mortar.No. KBS Pg No 140 ,Item No 9.27.								
Culvert								
Yogesh Nagar	Cum	2	5.00	0.45	0.60	2.70		
12th Cross Road								
Basic rate	351.00							
Area weightage 6%	21.06							
5km lead & Lift= 57+(2*1.28*5)	69.80							
Sub Total	441.86							
Total						2.70	441.86	1193.02

KSRRB M200-12.2. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, stacking the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M-20.MORTH Specification No. 202. Page No. 139, Item No.18.18 and Pg No.136, Item No.17.4,17.1 (5km lead = 57+2*1.28X5)

Culvert Deck Slab								
Yogesh Nagar								
12th Cross Road	Cum	1	5	1.5	0.2	1.5		
Basic rate	557.00							
Area weightage 6%	33.42							
5km lead & Lift= 57+(2*1.28*5)	69.80							
Sub Total	660.22							
Total						1.50	660.22	990.33

KSRRB 300-1. **Earthwork excavation by manual means for roads,** drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1) 5km lead= 57+2.0x1.28x5 =69.80

New Drain								
Nagarajappa Layout								
1st Cross Road	Cum	2	49	1.05	1.05	108.05		
2nd Cross Road	Cum	2	65	1.05	1.05	143.33		
Vayunandhana Layout								
1st Cross Road	Cum	1	89	1.05	1.05	98.12		
3rd Cross Road	Cum	1	92	1.05	1.05	101.43		
Yogesh Nagar								
11th Cross Road	Cum	2	34	1.05	1.05	74.97		
9th Cross Road	Cum	2	21	1.2	1.05	52.92		
7th Cross Road	Cum	2	21	1.2	1.05	52.92		
10th Cross Road	Cum	2	35	1.2	1.05	88.20		
12th Cross Road	Cum	2	32	1.2	1.05	80.64		
Netaji Nagar								
1st Main Road 4th Cross	Cum	2	59	1.2	1.05	148.68		
Cross Road	Cum	2	53.5	1.2	1.05	134.82		
New Culvert								

Scanned by TapScanner

Description of work	Unit	Measurement No.	L	B	D	Qty	Rate	Amount
Nagarajappa Layout								
2nd Cross Road	Cum	2	6.5	1.5	1.1	21.45		
Yogesh Nagar								
12th Cross Road	Cum	1	5	1.8	1.10	9.90		
Netaji Nagar								
Cross Road	Cum	1	5.2	1.8	1.10	10.30		
	130.00							
Rate per	7.80							
Amt as per Page 6/6								
5Km lead & LHP=	69.80							
5Km lead (Sand)								
Sub Total	207.60							
Total						1125.72	207.60	233699.16
4 KSRRB M2100 POC 1 KSRRB M2100-10. Providing and laying Plain cement concrete of mix1:3:6 with OPC cement @ 220kgs. with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.45cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of materials,labour, HOM curing form work, Scaffolding and Centering complete as per specifications,MORTH Specification No. 2100 Pg no:222 Item no:27.18								
New Drain								
Nagarajappa Layout								
1st Cross Road	Cum	2	49	1.05	0.15	15.44		
2nd Cross Road	Cum	2	65	1.05	0.15	20.48		
Vayunandhana Layout								
1st Cross Road	Cum	1	89	1.05	0.15	14.02		
3rd Cross Road	Cum	1	92	1.05	0.15	14.49		
Yogesh Nagar								
11th Cross Road	Cum	2	34	1.05	0.15	10.71		
9th Cross Road	Cum	2	21	1.20	0.15	7.56		
7th Cross Road	Cum	2	21	1.20	0.15	7.56		
10th Cross Road	Cum	2	35	1.20	0.15	12.60		
12th Cross Road	Cum	2	32	1.20	0.15	11.52		
Netaji Nagar								
1st Main Road 4th Cross	Cum	2	59	1.20	0.15	21.24		
Cross Road	Cum	2	53.5	1.20	0.15	19.26		
New Culvert								
Nagarajappa Layout								
2nd Cross Road	Cum	2	6.5	1.50	0.15	2.93		
Yogesh Nagar								
12th Cross Road	Cum	1	5	1.80	0.15	1.35		
Netaji Nagar								
Cross Road	Cum	1	5.2	1.80	0.15	1.40		
For CC Road								
Amruthahalli Janatha								
Cross Road	Cum	1	33.00	1.80	0.15	8.91		
Vayunandhana Layout								
1st Cross Road	Cum	1	89.00	4.30	0.15	57.41		
3rd Cross Road	Cum	1	92.00	3.50	0.15	48.30		
Yogesh Nagar								
11th Cross Road	Cum	1	34.00	4.80	0.15	24.48		
9th Cross Road	Cum	1	21.00	4.40	0.15	13.86		
7th Cross Road	Cum	1	21.00	4.50	0.15	14.18		
10th Cross Road	Cum	1	35.00	3.90	0.15	20.48		

Scanned by TapScanner

Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
12th Cross Road	Cum	1	32.00	4.40	0.15	21.12		
Netaji Nagar								
Cross Road	Cum	1	53.50	4.30	0.15	34.51		
Mariyanna Palya								
Antony Church Main Road (Green Elite Opposite)	Cum	1	49.00	4.60	0.15	33.81		
Antony Church Main & Cross Road	Cum	1	116.00	4.60	0.15	80.04		
Kuvempu Nagar								
1st A Cross Road	Cum	1	47.00	3.50	0.15	24.68		
2nd A Cross Road	Cum	1	66.00	4.00	0.15	39.60		
3rd A Cross Welcome Fashion Shop	Cum	1	66.00	3.00	0.15	29.70		
1st Cross Road	Cum	1	94.00	4.60	0.15	64.86		
Jakkuru								
5th Cross Road	Cum	1	55.00	3.90	0.15	32.18		
7th Cross Road	Cum	1	48.00	3.00	0.15	21.60		
6th Cross Road	Cum	1	99.00	3.00	0.15	44.55		
Cross Road	Cum	1	55.00	3.30	0.15	27.23		
Cross Road	Cum	1	34.00	5.50	0.15	28.05		
4th Cross Road	Cum	1	108.00	4.50	0.15	72.90		
1st Cross Road Near Temple	Cum	1	37.00	4.70	0.15	26.09		
Basic rate	5115.00							
Area weightage 6%	306.90							
Sub Total	5421.90							
Total						**929.05**	**5421.90**	**5037210.77**

5 Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification No. 1500, 1700, 2200. Including Cost of material, Labour, HOM complete as per Specification-WALL & Bottom thickness 15Cm(Item No 37.59.2 page no 271)

New Drain								
Bottom Raft								
Nagarajappa Layout								
1st Cross Road	Cum	2	49.00	1.05	0.15	15.44		
2nd Cross Road	Cum	2	65.00	1.05	0.15	20.48		
Vayunandhana Layout								
1st Cross Road	Cum	1	89.00	1.05	0.15	14.02		
3rd Cross Road	Cum	1	92.00	1.05	0.15	14.49		
Yogesh Nagar								
11th Cross Road	Cum	2	34.00	1.05	0.15	10.71		
9th Cross Road	Cum	2	21.00	1.20	0.15	7.56		
7th Cross Road	Cum	2	21.00	1.20	0.15	7.56		
10th Cross Road	Cum	2	35.00	1.20	0.15	12.60		
12th Cross Road	Cum	2	32.00	1.20	0.15	11.52		
Netaji Nagar								
1st Main Road 4th Cross	Cum	2	59.00	1.20	0.15	21.24		
Cross Road	Cum	2	53.50	1.20	0.15	19.26		
Side Walls								
Nagarajappa Layout								
1st Cross Road	Cum	4	49	0.15	0.75	22.05		
2nd Cross Road	Cum	4	65	0.15	0.75	29.25		
Vayunandhana Layout								
1st Cross Road	Cum	2	89.00	0.15	0.75	20.03		

Scanned by TapScanner

	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
	3rd Cross Road	Cum	2	92.00	0.15	0.75	20.70		
	Yogesh Nagar								
	11th Cross Road	Cum	4	34.00	0.15	0.75	15.30		
	9th Cross Road	Cum	4	21.00	0.15	0.75	9.45		
	7th Cross Road	Cum	4	21.00	0.15	0.75	9.45		
	10th Cross Road	Cum	4	35.00	0.15	0.75	15.75		
	12th Cross Road	Cum	4	32.00	0.15	0.75	14.40		
	Netaji Nagar								
	1st Main Road 4th Cross	Cum	4	59.00	0.15	0.75	26.55		
	Cross Road	Cum	4	53.50	0.15	0.75	24.08		
						Sub Total	361.87		
	New Culvert								
	Bottom Raft								
	Nagarajappa Layout								
	2nd Cross Road	Cum	2	6.50	1.50	0.20	3.90		
	Yogesh Nagar								
	12th Cross Road	Cum	1	5.00	1.80	0.20	1.80		
	Netaji Nagar								
	Cross Road	Cum	1	5.20	1.80	0.20	1.87		
	Side Walls								
	Nagarajappa Layout								
	2nd Cross Road	Cum	4	6.5	0.20	0.75	3.90		
	Yogesh Nagar								
	12th Cross Road	Cum	2	5	0.2	0.75	1.50		
	Netaji Nagar								
	Cross Road	Cum	2	5.2	0.2	0.75	1.56		
						Sub Total	14.53		
	Basic rate	6670.00							
	Area weightage 6%	400.20							
	Sub Total	7070.20							
	Total						376.40	7070.20	2661219.74
6	KSRB M2200-6 Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. MORTH Specification NO.1600&2200Specification No. Pg No.229 Item No.28.8.2								
	For Drain	Cum	From item no.5				361.87		
		kg	Steel assumed 60Kg/Cum of Concrete				21712.05		
		tonne					21.71		
	For Culvert	Cum	From item No 05				14.53		
		kg	Steel assumed 90Kg/Cum of Concrete				1307.88		
		tonne					1.31		
	Basic rate	61365.00							
	Area weightage 6%	3681.90							
	Sub Total	65046.90							
	Total						23.02	65046.90	1497375.08

Scanned by TapScanner

	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)								
	Nagarajappa Layout								
	1st Cross Road	Sqm	2	49	0.75		73.50		
	2nd Cross Road	Sqm	2	65	0.75		97.50		
	Vayunandhana Layout								
	1st Cross Road	Sqm	1	89	0.75		66.75		
	3rd Cross Road	Sqm	1	92	0.75		69.00		
	Yogesh Nagar								
	11th Cross Road	Sqm	2	34	0.75		51.00		
	9th Cross Road	Sqm	2	21	0.9		37.80		
	7th Cross Road	Sqm	2	21	0.9		37.80		
	10th Cross Road	Sqm	2	35	0.9		63.00		
	12th Cross Road	Sqm	2	32	0.9		57.60		
	Netaji Nagar								
	1st Main Road 4th Cross	Sqm	2	59	0.9		106.20		
	Cross Road	Sqm	2	53.5	0.9		96.30		
	Data Rate	**2337.00**							
	Total						**756.45**	**2337.00**	**1767823.65**
8	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incha								
	New Culvert								
	Nagarajappa Layout								
	2nd Cross Road	Sqm	2	6.5	1.2		15.60		
	Yogesh Nagar								
	12th Cross Road	Sqm	1	5	1.5		7.50		
	Netaji Nagar								
	Cross Road	Sqm	1	5.2	1.5		7.80		
	Data rate	**5418.00**							
	Total						**30.90**	**5418.00**	**167416.20**
9	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specifications. MORTH Specification No. 202(P.No.140- I.No.18.47) & Pg No.136, Item No.17.4,17.1								
	Yogesh Nagar								
	11th Cross Road	Cum	1	34.00	4.80	0.30	48.96		
	9th Cross Road	Cum	1	21.00	4.40	0.30	27.72		
	7th Cross Road	Cum	1	21.00	4.50	0.30	28.35		
	10th Cross Road	Cum	1	35.00	3.90	0.30	40.95		
	12th Cross Road	Cum	1	32.00	4.40	0.30	42.24		
	Mariyana Palya								
	Antony Church Main & Cross Road	Cum	1	116.00	4.60	0.30	160.08		
	Kuvempu Nagar								
	1st A Cross Road	Cum	1	47.00	3.50	0.30	49.35		
	2nd A Cross Road	Cum	1	66.00	4.00	0.30	79.20		
	3rd A Cross Welcome Fashion Shop	Cum	1	66.00	3.00	0.30	59.40		
	1st Cross Road	Cum	1	94.00	4.60	0.30	129.72		

Scanned by TapScanner

	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
	7th Cross Road	Sqm	1	48.00	3.00		144.00		
	6th Cross Road	Sqm	1	99.00	3.00		297.00		
	Cross Road	Sqm	1	55.00	3.30		181.50		
	Cross Road	Sqm	1	34.00	5.50		187.00		
	4th Cross Road	Sqm	1	108.00	4.50		486.00		
	1st Cross Road Near Temple	Sqm	1	37.00	4.70		173.90		
		6.00							
	Basic rate	0.36							
	Area weightage 6%	6.36							
	Sub Total						3962.35	6.36	25200.55
	Total								
2	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications Clause 401 of MORTH V Revision.(I No-20.5,P No-153)								
	Amruthahalli Janatha								
	Cross Road	Cum	1	33.00	1.80	0.15	8.91		
	Vayunandhana Layout								
	1st Cross Road	Cum	1	89.00	4.30	0.15	57.41		
	3rd Cross Road	Cum	1	92.00	3.50	0.15	48.30		
	Netaji Nagar								
	Cross Road	Cum	1	53.50	4.30	0.15	34.51		
	Mariyana Palya								
	Antony Church Main Road (Green Elite Opposite)	Cum	1	49.00	4.60	0.15	33.81		
		1882.00							
	Basic rate	112.92							
	Area weightage 6%	1994.92							
	Sub Total						182.93	1994.92	364935.70
	Total								
3	Cement concrete pavement.Construction of un-reinforced plain cement concrete for pavement, using a grade concrete M30 over a prepared base with OPC coarse aggregate @ 0.69cum fine aggregate @ 0.46cum,coarse and fine aggregate confirming to IS:383-2016,with superplastisiser @3lts confirming to IS9103-2008.mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine,and curing including cost of all materials,labour,hire charges of machineries,all lead and lift charges etc., complete as per specifications. - do with OPC at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.46cum Pg No.176Item No.22.6.1								
	Amruthahalli Janatha Colony								
	Cross Road	Cum	1	33.00	1.80	0.15	8.91		
	Vayunandhana Layout								
	1st Cross Road	Cum	1	89.00	4.30	0.15	57.41		
	3rd Cross Road	Cum	1	92.00	3.5	0.15	48.30		

Scanned by TapScanner

Description of work	Unit	Measurement				Qty	Rate	Amount
		No.	L	B	D			
Yogesh Nagar								
17th Cross Road	Cum	1	34.00	4.80	0.15	24.48		
6th Cross Road	Cum	1	21.00	4.40	0.15	13.86		
7th Cross Road	Cum	1	21.00	4.50	0.15	14.18		
19th Cross Road	Cum	1	35.00	3.90	0.15	20.48		
12th Cross Road	Cum	1	32.00	4.40	0.15	21.12		
Nehaji Nagar								
Cross Road	Cum	1	53.50	4.30	0.15	34.51		
Marigowa Palya								
Antony Church Main Road (Green Elite Opposite)	Cum	1	49.00	4.60	0.15	33.81		
Antony Church Main & Cross Road	Cum	1	116.00	4.60	0.15	80.04		
Narayana Nagar								
1st A Cross Road	Cum	1	47.00	3.50	0.15	24.68		
2nd A Cross Road	Cum	1	66.00	4.00	0.15	39.60		
3rd A Cross Welcome Fashion Shop	Cum	1	66.00	3.00	0.15	29.70		
1st Cross Road	Cum	1	94.00	4.60	0.15	64.86		
Jakkuru								
5th Cross Road	Cum	1	55.00	3.90	0.15	32.18		
7th Cross Road	Cum	1	48.00	3.00	0.15	21.60		
6th Cross Road	Cum	1	99.00	3.00	0.15	44.55		
Cross Road	Cum	1	55.00	3.30	0.15	27.23		
Cross Road	Cum	1	34.00	5.50	0.15	28.05		
4th Cross Road	Cum	1	108.00	4.50	0.15	72.90		
1st Cross Road Near Temple	Cum	1	37.00	4.70	0.15	26.09		
Basic rate	4916.00							
Area weightage 6%	294.96							
sub Total	5210.96							
Total						768.50	5210.96	4004635.79
							Grand Total	16749079.28
							DPR Charges (1% of estimated cost)	200000.00
							Project management And Consultancy Charges(1% of estimated cost)	200000.00
							GST Charges (12% of estimated cost)	2009889.51
							Tender Premium (5% of estimated Cost)	837453.96
							Miscellenious and rounding	3577.24
							Total Amount	20000000.00
							RUPEES TWO CRORE ONLY	

Administrative Approval

Accorded For Rs. 2 Crores Only

Head of A/C 91878 Project management And Consultancy Charges

CER NO : 92 Dt: 04/12/2020

EE (Plg)

CERTIFICATE:

1) The work spot has been inspected and found to be necessary
2) The work spot comes under B.B.M.P
3) The provisions made in the estimate are necessary and minimum
4) The estimate is based on C.S.R of 2018-2019,Issue rates and Data Rates.

Technical Sanction

Accorded For Rs. 2 Crores Only

Head of A/C 91878

CER NO : 92 Dt: 20.08.2020

TA | CE (YNK)

Assistant Engineer
BBMP

Assistant Executive Engineer
BBMP

Executive Engineer
BBMP

Scanned by TapScanner